

Offer for CCTV setup

Sl. No.	Description	Make	Rate (Rs.)	VAT / CST (%)	VAT / CST Amt. (Rs.)	Unit Total (Rs.)	Qty	Unit	Total (Rs.)
Head End Equipment									
1	8 Channel DVR	HIKVISION/Eqvt.					1	no	
2	HDD 2TB	SEAGATE/WD/Eqvt.					1	no	
3	UPS (700 / 600 VA)	lball/Eqvt.					1	no	
Total									
Camera									
4	PTZ DOME IR CAMERA	HIKVISION/Eqvt.					1	no	
5	SMPS POWER SUPPLY for PTZ camera (24 V 3.33 A)	HIKVISION/Eqvt.					1	no	
6	Bracket for PTZ camera	HIKVISION/Eqvt.					1	no	
7	IR DOME Camera	HIKVISION/Eqvt.					3	nos.	
8	SMPS for IR Dome Camera (12V 1.25 A)	ACCORD/Eqvt.					3	nos.	
Total									
Cables									
9	RG6 CABLE (Coil of 91 Mtrs)	PLUS/ LEADER/Eqvt.					3	lot	
10	POWER CABLE (Coil of 91 Mtrs) 0.75 mm	MESCAB/Eqvt.					3	lot	
11	POWER CABLE for Server (Coil of 91 Mtrs)	Reputed					3	lot	
12	CAT 6 Cable (coil of 100 mtrs.)	PLUS/Eqvt.					1	lot	
Total									
Fittings									
13	HDPI Pipe	Reputed					1	lot	
14	PVC casing/ Clipping (25 mm)	Reputed					1	lot	
15	Fitting Clip & Elbow Tee	Reputed					1	lot	
Total									
Installation and Commissioning									

16	Cable Laying, Termination, Installation & Commissioning at site						1	Job	
Grand Total									
Note: Quantity of Item No. 9,10,11 & 12 will be considered as per actual consumption at site, rounded off to the nearest higher coil quantity.									

Site Location : North Bengal

Delivery : At Site.

Network diagram of total installation with necessary detailing is to be submitted immediately.

In case, site visit is required before submitting the network diagram, and offer, the same is to be arranged by the vendor at their own cost.

Payment Terms : 95% payment will be made after commissioning and satisfactory service of the complete system.

Balance 5% payment will be considered as 'Security Deposit' and released only after successful completion of one year from the date of completion of I & C

Warranty : Two years from the date of completion of the said work.

All purchases / Guarranty / warranty papers / License is to be submitted in favour of Webel Mediatronics Limited.

Training on Handling operation of the total system is to be given till satisfaction.

Delivery, I & C, and training of the entire system is to be completed by 07.06.2014.