

Installation-commissioning of Addressable Fire Detection & Alarm System at State Archive Building, 6 Bhawani Datta Lane Kolkata-73					
S.N O.	Item(s) to be installed	Qty	Location	Unit Price	Total Price
1	<b>Fire Alarm Control panel</b> with 6 loops and battery back up for upto 72 hours. <b>Make: Schrack Seconet, Austria</b>	1nos	Ground Floor		
2	Addressable type multisensor detector with base for use as heat or smoke or combined. <b>Make: Schrack Seconet, Austria</b> Base is to be mounted on ceiling	623nos	Ground Floor- 90, 1st Floor-136, 2nd Floor-167, 3rd Floor-65, 4th Floor-158, 5th floor- 7		
3	Linear Beam Smoke Detector along with its accessories including power connection, input / output connection <b>Make: Schrack Seconet, Austria</b>	4nos	Ground Floor		
4	Manual Call Point (MCP) <b>Make: Schrack Seconet, Austria</b>	14nos	Gnd Flr- 3 1st Flr-2, 2nd Flr-3, 3rd Flr-3, 4th Flr-2, 5th Flr-1		
5	Addressable Loop Powered multi tone sounder <b>Make: Schrack Seconet, Austria</b>	14nos	Gnd Flr- 3 1st Flr-2, 2nd Flr-3, 3rd Flr-3, 4th Flr-2, 5th Flr-1.		
6	I/O Loop module, Make Schrack & Seconet	5nos	Ground Floor		
7	Addressable Loop Powered multi tone flasher/ strobe <b>Make: Schrack Seconet, Austria</b>	14nos	Gnd Flr- 3 1st Flr-2, 2nd Flr-3, 3rd Flr-3, 4th Flr-2, 5th Flr-1		
8	Response Indicator (RI) for detectors above False Ceiling <b>Make: Reputed</b>	6nos	4th Floor -6		
9	1 sqmm. 2 Core thickness twisted pair shielded/screened Cable <b>Make: Reputed</b>	4644mtr			
10	20 mm MS Conduit (ISI) <b>Make: Reputed</b>	4644mtr			
11	Installation of Auto Dialer for SMS Alert system	1no	Ground Floor		
12	CAT6 cable laying from FDA Panel to Director's room	20mtr	2nd Floor(Director Room)		
<b>Total price (exclusive of tax)</b>					
<b>Total price (inclusive of service tax @14%)</b>					
Offer validity:					
<b>Completion Schedule:</b>					
I & C Support					